



700 West Liberty Street | Louisville, KY 40203-1911

Phone: 502.540.6000 | LouisvilleMSD.org

CLIFTON HEIGHTS FORCE MAIN EXTENSION PROJECT

General Information

Contractor:	TSI Construction Inc.
Construction Contract Amount:	\$2,183,300
Construction Contract Start:	May 2017
Construction Completion:	February 2018
MSD Project Manager:	Meskerem Eshetu, PE (502)-540-6496 (office)
Design Engineer:	Todd Solomon, PE/ GRW Engineers
Construction Inspector:	Alan Winchell PE (502) 438-6914 (cell)

- This project is part of MSD's Integrated Overflow Abatement Plan and is required per our Federal Consent Decree. The Consent Decree deadline for completion is December 31, 2018.
- The primary component of this project is the construction of approximately 3,600 linear feet of 20- inch Force Main Pipe.
- Other components include two manholes, flood closure crossing, and Bridge crossing, and modification of CSO 088, and CSO 131 Structures.
- When completed it will accommodate wet weather flows within the project area to limit the occurrence of overflows of CSOs 088, 131, 132, 154, and 167.
- Project will require excavation work within the pavements on Mellwood Avenue; Brownsboro Road (between Mellwood Avenue and Story Avenue); Story Avenue (between Frankfort Avenue and Cabel Street); and on Cabel Street.